

Attachment 19

TOWN OF WESTON

WESTON, CONNECTICUT

A PROPOSED DOG PARK

DAVIS HILL ROAD

TRAFFIC IMPACT ANALYSIS

FINAL DRAFT

PREPARED FOR
BOARD OF SELECTMEN

PREPARED BY:
WESTON TOWN ENGINEER'S OFFICE
John Conte P.E.

AUG 01 2017

TABLE of CONTENTS

Number	Page
1. INTRODUCTION	1
2. EXISTING CONDITIONS	2
Land Uses	2
Existing Roadways	2
Traffic Counts	3
Capacity Analysis	3
Accident Data	5
Existing Sight Distance	5
3. PROPOSED DEVELOPMENT TRAFIC IMPACTS	6
Analysis Methodology and Assumptions	6
Trip Generation and Distribution	6
Future Year (2022) Build Traffic Volumes	8
4. STUDY CONDITIONS	8
5. RECOMMENDED IMPROVEMENTS	8
6. REFERENCES	53
APPENDICES	
A. Site Plans	10
B. Location Map	17
C. Topographic map	19
D. Traffic Counts	21
E. Time Gap Study	28
F. Accident Data	33
G. Safe Stopping Sight Distance	35
H. Highway Capacity Manual Classifications	38
I. Future Area Growth Map	41
J. Highway Users Guide	42

K. Highway Capacity Software Years 2017-2022	44
L. Intersection Analysis	51

FIGURES

1. Peak Hour Volume Year 2022	9
-------------------------------	---

Table

1. Summary Sight Distance Analysis	5A
------------------------------------	----

INTRODUCTION

This report documents the findings and conclusions of a traffic impact analysis conducted for the Board of Selectmen for a proposed 3.5 acre dog park submitted to the Board for site plan approval. This facility is to be located on a large tract of land, Assessor's Map 17, Block 1, Parcel 17, located south of Lords Highway East. The entrance/exit driveway is to be located on Davis Hill Road, across the street from house number 146 Davis Hill Road.

The parcel has frontage on both Davis Hill Road and Lords Highway East, however, only a portion of the property on Davis Hill Road is included in this development (see Appendix A site plans). Access to the site will be restricted to Davis Hill Road.

The dog park will be located on a Town-owned parcel totaling over 35 acres. There are numerous stone walls within the property, sectioning off the property into square parcels. The dog park will utilize two of the sectioned-off parcels. A 15 car parking lot will be located on the 2.5 acre section which is adjacent to Davis Hill Road. The park itself will be located on a sectioned-off parcel totaling 3.5 acres. The park will be adjacent to the parking lot. A dog park use is typically utilized more extensively on the weekends during the peak periods when Davis Hill Road traffic volumes are lower than on weekdays. The site users also tend to arrive or depart during non-commuter peak traffic hours during the weekdays, as well, thus not adding to the highest travel hours on Davis Hill Road.

Currently, the site property is undeveloped. A linear pave and gravel driveway will extend to the parking area from Davis Hill Road, as shown in the plans found in Appendix A. All site traffic will utilize the dog park driveway with the intersection of Davis Hill Road to enter and exit the site.

The anticipated build-out would likely occur within a year or two, and certainly within five years, full traffic use will be developed for the area. See Appendix B – location map for project location. Discussions with the Board of Selectmen included an agreement that an in-depth analysis of the site driveway intersection on Davis Hill Road would be conducted to determine any impacts to that intersection. Other intersections are approximately 0.2 miles from the site driveway and are considered remote from the site access/egress. Therefore, the site driveway, where all site trips will enter Davis Hill Road, is to be the concentration of this study.

This traffic report has been prepared for submission to the Board of Selectmen, the review agent for site plan projects concerning Town-owned properties. The traffic-related issues addressed in this report are:

- Collect traffic and speed counts on Davis Hill Road near the proposed site driveway intersection for 24 hours during weekdays.
- Analyze the road/site driveway intersection capacity to handle anticipated traffic volumes without the project, during the peak AM, MD (mid-day) and PM periods in the year 2022, as counted for weekdays.

- Project future traffic in five years, 2022, with full build-out using an increase of 1% growth per year for a period of 5 years, for the background traffic at the study intersection, during AM, MD, and PM peak weekday travel hours.
- Estimate site-generated traffic volumes and their anticipated distribution onto Davis Hill Road.
- Review of accident history at the Davis Hill Road/site driveway intersection and any accidents along Davis Hill Road nearby to the study intersection.
- Measurement of available sight distance for site driveway onto Davis Hill Road.

Evaluation and analysis included a field review of existing conditions (i.e. lane widths, road layout and alignments), collection of two-way, hour per hour and 24 hour traffic counts on Davis Hill Road; and the creation of AM, MD, and PM peak hour weekday counts. Since the study intersection does not exist today, the 24 hour counts include all traffic to be analyzed for the dog park scenario. Capacity analysis of pre-versus post-construction was conducted to determine what effect the site will have on Davis Hill Road's ability to accommodate the new site traffic. A review of accident data for the study intersection of the dog park driveway and Davis Hill Road is included. The traffic analysis concentrated on the single intersection that is most likely to be impacted by the proposed development, namely

- Davis Hill Road at proposed site driveway.

EXISTING CONDITIONS

The existing roadway, Davis Hill Road and the proposed intersection to the site were evaluated, including land uses, geometrics and traffic volumes.

LAND USES

Located within the vicinity of the proposed development along Davis Hill Road, there are residential frontage lots with no new residential development. There are only two vacant parcels located on Davis Hill Road; one 14+ acre parcel with frontage on Davis Hill Road and Hill Farm Road and the other is a 13+ acre parcel with a large wetland area (see map in Appendix I growth area map).

EXISTING ROADWAYS

The roadways servicing the study area, which may be most impacted by the proposed project, include Davis Hill Road and the site driveway.

DAVIS HILL ROAD

Davis Hill Road is a Town-owned, two-lane, two-way rural roadway approximately 18-22 feet in width with only one area at 18 feet all other areas are at 22 feet, spanning between Valley Forge Road to the north and Steep Hill Road to the south. The site driveway is approximately 0.2 miles south of the intersection of Davis Hill Road and Lords Highway East.

Several minor roads intersect Davis Hill Road within a half a mile of the site study intersection, with minor traffic volumes added to the Davis Hill Road commuter traffic during weekday AM and PM peak travel hours. Appendix D shows the hourly traffic volumes counted adjacent to the proposed site driveway, with 24-hour volume graphs indicating a heavier weekday commuter pattern southbound in the AM and northbound in the PM peak hours. Midday weekday traffic volumes dropped. The posted speed limit on Davis Hill Road is 25 mph, approaching the study intersection for both directions.

PROPOSED SITE DRIVEWAY

The proposed site driveway is to be an 18-foot wide paved and gravel surface intersecting Davis Hill Road. The site driveway will traverse the site to the dog park area. Stopping sight-distance measurements at this intersection are provided in this report.

TRAFFIC COUNTS

In order to quantify existing conditions and identify predominant traffic patterns, since there is no site traffic using the driveway today, the Town Engineer's office and the Weston Police Dept. had 24-hour, 2-way automatic traffic recorder (ATR) counts performed from the afternoon on Wednesday, May 31, 2017, to Friday morning on June 1, 2017 (see Appendix D) to obtain full 24 hour, hour by hour, traffic volume for Davis Hill Road with peak periods utilized as turning movement traffic events at the proposed driveway. On Wednesday, May 31, 2017, Godfrey Road East was closed to thru traffic from 8am to 4pm, with only local traffic being allowed to pass. Godfrey Road East is located north of Davis Hill Road. The two roads are connected primarily by Valley Forge Road. Catbrier Road and Raven Wood Road are connected to Davis Hill Road by way of Lords Highway East. Manual traffic counts were conducted on Davis Hill Road, Wednesday, May 31, 2017, during peak hours of 7:30am to 9:30am, 12:30am to 1:30pm, and 3:30pm to 5:30pm. Manual peak-hour counts were compared to the automated peak-hour counts of June 1, 2017, to determine if the road closure of Godfrey Road East had any impact of increasing traffic volumes. This comparison was done to forecast any increase in future traffic volumes once the dog park is in full operation due to area road closures. The comparison showed a decrease in traffic volumes during the closure of Godfrey Road East.

CAPACITY ANALYSIS

Using the turning movements traffic counts shown in appendix “D” existing conditions capacity analyses were performed for the existing study intersection. The analyses were performed using the Highway Capacity Software by Trafficware. The Town of Weston does not have in its possession the Highway Capacity Software. To utilize that particular software the town engineer’s office incorporated the help of the engineering staff of the Western Connecticut Council of Governments located in Sandy Hook Connecticut. The engineering staff at the council provided assistance and software to analyze the pre and post traffic conditions of the proposed Weston Dog Park.

Capacity analysis assesses traffic operations in terms of Level of Service (LOS), which is a concept that was developed by transportation engineers to quantify the level of operation of intersections and roadways. LOS measures are classified in grades “A” through “F” indicating a range of operation from LOS “A”, signifying the least congested level of operation, to “F”, the worst, which is considered failure.

LEVEL of SERVICE	
Criteria for Unsignalized Intersections	
LEVEL of SERVICE (LOS)	CONTROL DELAY Per Vehicle (SEC)
A	0-10
B	>10 and <15
C	>15 and <25
D	>25 and <35
E	>35 and <50
F	>50

Generally, LOS “D” is considered the threshold limit of acceptable operation for intersections.

The Highway Capacity Manual classifies roadways into three classifications- Class I, Class II and Class III (see appendix H). Davis Hill Road is classified as a Class III two lane highway. The software takes into account the most critical peak hour of the number of vehicles using the roadway. In this case it was determined by the town engineer and the engineering staff at the council that the most critical hour was from 5pm to 6pm. The software also takes into account lane width, grades, terrain type, access point density (driveways entering Davis Hill Road within the study area). With that information the program determines the percent free flow speed (PFFS). The PFFS is then compared to the level of service classification for PFFS for a class III two lane highway (see appendix J two-lane highways users’ guide).

The analysis for the year 2017 no build condition on Davis Hill Road found that the PFFS was a 90.4%. Based on the highway capacity manual a PFFS of 90.4% is a level of service “B”. For the project year of 2022 the PFFS was 90.1% indicating a level of service “B” for the study area (see appendix K). The engineering staff at the council also did a computer run conducting an analysis of the proposed intersection of Davis Hill Road and the proposed driveway to the dog park for

the year 2022 (see appendix L). The analysis indicated the level of service for the intersection for the year 2022 is LOS “A”.

Based on the information provided above and in appendix “K” we can see with the highway capacity manual software that the Davis Hill Road movements experience excellent levels of service, LOS “B”. Volumes on this road during weekday’s peak at morning and evening commute hours, however the volumes are relatively low with sizable reserve capacity to accommodate significantly more traffic before delays are noticeable.

ACCIDENT DATA

Accident data for the years 2012 through 2017 was retrieved from the Weston Police Dept.’s accident record system for the entire length of Davis Hill Road. Those accidents are highlighted in Appendix F. The print out from the Police Dept. shows where accidents occurred in front of houses by house numbers. Where no house number appears, an accident occurred in an area on Davis Hill with no houses nearby. The dog park entrance is located across the street of house number 146. The accident report indicates most accidents occurred at the southern end of Davis Hill Road. One accident occurred north of the dog park. Since the new driveway does not exist, we looked for any accidents close to the proposed driveway location and found none.

EXISTING SIGHT DISTANCE

Existing sight distances at intersecting roadways or driveways are an important factor in the safety of both an exiting vehicle and an approaching vehicle. As part of this report, the Town Engineer’s office has measured in the field sight distance at the location of the proposed site driveway on Davis Hill Road. The measured sight distance for a vehicle exiting the site driveway is shown in Table 1.

Two types of sight distance requirements for intersecting roadways or driveways used in this report are the Connecticut Department of Transportation Highway Design Manual and the Town of Weston Subdivision Regulations. The stopping sight distance (SSD) is based on the time it takes an approaching vehicle to come to a complete stop, once it has seen an object. For a 30 mph speed limit, the SSD for oncoming traffic to safely stop is 200 feet on a flat roadway (see Appendix G). However, Davis Hill Road has a slope of 4.8% down grade approaching from the north to the site intersection, requiring a SSD of 215 feet and a 3.2% upgrade slope approaching from the south to the site intersection, requiring a SSD of 200 feet. The area at the proposed intersection is a level grade. Since the Town of Weston is exempt from its zoning regulations, it is recommended to use the CT DOT regulations. The sight distance for vehicles approaching from the south exceeds the criteria set forth by the CT DOT. The sight distance for vehicles approaching from the north does not meet the criteria. To correct the sight distance to the north,

TABLE 1**Summary of sight Distance Analysis****Stopping Sight Distance (Feet)-30 MPH**

Location	CT D.O.T Criteria	Town of Weston Criteria	Measured SSD Distance	SSD Criteria Met
Site Driveway at Davis Hill Road				
From the North	215	250	177	No
From the South	200	250	400	Yes

Note:

The Town of Weston requires a 250 foot
Sight distance for new subdivision roads
And driveways.

numerous trees must be removed and the existing shoulder must be lowered to provide the 215 feet of clear sight line (see Appendix C).

It should be pointed out that the traffic count and speed results in Appendix D indicate that the 85th percentile speed on Davis Hill Road is 31:45mph for the north bound lane and 27:03mph for the south bound lane. That speed should be police-controlled and it is recommended that 25 mph speed limit signs be placed a distance of 250 feet minimum from the proposed driveway in the north and south bound lanes. At the present time, there is only one 25 mph sign at the southern end of Davis Hill Road. Also, it is recommended that Park Entrance Ahead signs be placed 300 feet from the proposed driveway in both directions to warn drivers of the site entrance ahead. Again, there were no reported accidents in the immediate vicinity of the proposed site driveway study intersection.

PROPOSED DEVELOPMENT TRAFFIC IMPACTS

Analysis Methodology and Assumptions

Traffic impacts have been estimated in order to determine the extent of change in traffic conditions caused by the development of this project. In order to make this determination, the following assumptions and methodology were employed:

- The proposed development will be built out within five years.
- Existing background traffic in the site area will grow by 1.0% per year for the 5 year study period.
- The existing year 2017 counts were expanded by 5.1% to arrive at the Future 2022 No-Build traffic volumes. Analysis of these future volumes without the site trips helps determine how well the intersection will operate even if the project is not constructed.
- Traffic generation estimates from the project were prepared for the critical weekday AM, MD and PM peak periods. Trip generation was also calculated from field counts of the Town of Easton Dog Park.
- Cumulative traffic impacts of the proposed project were then determined by superimposing the project-generated traffic onto the Future 2022 No-Build background adjusted traffic, to create the “2022 Build” scenario for the study intersection.

TRIP GENERATION AND DISTRIBUTION

Trip generation estimates were prepared for the proposed development. Various studies have determined that particular land uses, such as residential and recreational land uses, exhibit certain traffic volume characteristics:

- 1) Total entering and exiting volume within a 12-hour period with parks open between sunrise and sunset.
- 2) Peak hour traffic characteristics. The traffic generation data is then compared to specific land use characteristics, such as the number of parking spaces and/or the gross square

footage of the park. This data was then utilized to develop site traffic volume estimates for this project.

To determine accurate traffic volumes caused by the operation of a dog park, the Town Engineer's office conducted field counts of the Easton Dog Park from 6:30am to 6:00pm on the date of Saturday June 10, 2017 for the entire day. The weather on June 10, 2017 was sunny and warm. Easton was chosen because of the similarities to Weston concerning zoning and population. Total vehicles for the time frame mentioned above were 18 vehicles.

For trip generation values of the total number of vehicles trips per day anticipated from the proposed dog park, the town engineer and the engineering staff from the council came up with an anticipated 25 trips per day. That calculation was based using the volume of traffic found at the Easton Dog Park taking into account the difference in population and the annual traffic growth to the year 2022. See calculations below.

DOG PARK TRIP GENERATION

$$18 \text{ trips/day} \times 10,179 = 24 \times 1.05\% = 25 \text{ trips/day} \\ 7,490$$

Measured @ x Population x 1% Annual = Trips per Day

Easton Dog Difference Traffic Growth
Park to 2022

(Weston Population 10,179)

(Easton Population 7,490)

Assuming 25% of ADT = Peak Hour

$$25 \times (0.25) = 6 \text{ Trips/Hour} = 3 \text{ North Bound} \\ 3 \text{ Southbound}$$

Peak hour volume 5pm to 6pm 2017

19 veh./hour North Bound 18 veh./hour South Bound

North Bound 19 veh. /hour 2017

20 veh. /hour 2022 (+5%)

+ 3 veh. /hour Left into Dog Park

23 veh./hour North Bound 2022

South Bound 18 veh./hour 2017

19 veh./hour 2022 (+5%)

+ 3 veh./hour Right into Dog Park

22 veh./hour South Bound 2022

See Figure No 1

FUTURE YEAR (2022) BUILD TRAFFIC VOLUMES

Site generated trips from this development were added to the Future (2022) No-build traffic volumes to arrive at Future (2022) Build traffic volumes. Those peak No-build and Build peak traffic volumes generated by the site use are illustrated in Figures 1 for weekdays. Growth rates are based on a 1% growth rate per year for a period of five years. The land surrounding the proposed dog park was evaluated to determine if there were large areas still under-developed (see Appendix I future area growth map). There are only two large parcels privately-owned with the area of the proposed dog park, a 14+ acre site and a 13+ acre site. The remaining areas are developed.

STUDY CONCLUSIONS

The analysis indicates that Davis Hill Road has sufficient capacity to accommodate the estimated traffic from the proposed dog park with no significant increased delay. The weekday volumes traveling on Davis Hill Road indicate a commuter pattern of morning peak traffic heading south and a return peak flow during the evening commute hours heading north. In winter months, if snow fall occurs, the parking lot will not be plowed, causing the closure of the park during winter, making it a seasonal use. If snow fall does not occur, the park will remain open during winter months.

RECOMMENDED IMPROVEMENTS

- 1) Clear the sight line north of the proposed driveway by removing trees and vegetation to the recommended distance in the report. Lower the shoulder in the same location to achieve the required sight line. See Sight Line Improvements Weston Dog Park Davis Hill Road.
- 2) Place 25 mph speed limit signs at the required distances from the proposed driveway in the south bound and north bound lanes, as indicated in this report.
- 3) Place warning signs stating Park Entrance Ahead at the required distances from the proposed driveway in the south bound and north bound lanes, as indicated in this report.


This report documents that the proposed intersection of Davis Hill Road at the site driveway can accommodate the proposed site traffic with little noticeable change in operational efficiency and safety.

Figure 1

Peak Hour Volume


Year 2022

5pm to 6pm



APPENDIX “A”

SITE PLANS




PROPERTY SURVEY
PREPARED FOR

THE TOWN OF WESTON
DAVIS HILL ROAD & LORD'S HIGHWAY
TOWN OF WESTON
AUG. 19, 2016
SCALE: 1" = 80'


THIS SURVEY MAP HAS BEEN PREPARED BY THE TOWN OF WESTON, CONNECTICUT, IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONNECTICUT DEPARTMENT OF CONSTRUCTION, AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS. IT IS A PROPERTY SURVEY BASED UPON A DEPENDENT RESURVEY OF THE TOWN OF WESTON, CONNECTICUT. THIS SURVEY MEETS CLASS A-2 TO THE BEST OF MY KNOWLEDGE. THIS MAP IS SUBSTANTIALLY CORRECT AND ACCURATE. PREPARED BY THE OFFICE OF THE TOWN CLERK, TOWN OF WESTON, CONNECTICUT. 35 HANBURY ROAD, WESTON, CT 06897. 720 871 1111. 100' 200'



LEGEND



DOG BACK AREA



Scale 1" = 20'

Town of Weston
 Site Plan
 Proposed Dog Park
 Davis Hill Road
 October 27, 2016




- Note
1. Boundary Survey by PAH, INC Land Surveyors
 2. Topographic Survey by John P. E. E.
 3. Wetland Soil Boundary by Chris L. Threlk Soil Scientist

- TEST PIT NO. 1 (TP NO. 1)
- 0'-2" Top Soil
 - 2'-30" Reddish brown Sandy Loam with Stone
 - 24" Ledge
 - No Groundwater
 - No Mottling
- TEST PIT NO. 2 (TP NO. 2)
- 0'-2" Top Soil
 - 2'-30" Reddish brown Sandy Loam with Stone
 - 30" Ledge
 - No Groundwater
 - No Mottling
- TEST PIT NO. 3 (TP NO. 3)
- 0'-2" Top Soil
 - 2'-30" Reddish brown Sandy Loam with Stone
 - 17'-38" Tan Greyish Loam Compacted
 - 38'-42" Grey Compacted Gravelly Loam with Stone
 - 38" Mottling
 - No Groundwater
 - No Ledge



Sight Line Plan



Parking Access Drive Profile

Town of Weston
 Proposed Dog Park
 Profiles
 of
 Access Drive & Sight Line
 Davis Hill Road October 27, 2016



SECTION 2.09

2.09.01 - Description: The area upon which the permanent structure and gravel shoulders are placed, including the subgrade, the concrete and asphalt shall be the bottom of the subgrade and the edge of pavement, as shown on the plan view of the proposed work. The work of construction of a permanent structure shall be performed at this point.

When present concrete barrier curb is to be permanently removed, the barrier curb shall be removed and the work performed on the area under the present concrete barrier curb.

When shoulders are to be reconstructed and the existing shoulder is to be removed, the work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

After all grading has been satisfactorily completed and all shoulders have been reconstructed, the work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

When no item for "Clearing and Grubbing" and no grading items appear in the proposal, the work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

2.09.02 - Construction Methods: All work and filling shall be done in accordance with the specifications for the work of reconstruction and the work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The dry density after compaction shall be as specified in the specifications for the work of reconstruction and the work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

SECTION 3.08

3.08.01 - Description: The base shall consist of one or more courses, each 6 inches (150 millimeters) in thickness, and shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

3.08.02 - Material: ¾ inch Processed Aggregate shall be used for the base and shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

3.08.03 - Construction Methods: The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

After the first course has been completed and bound as required, the second course shall be placed in order to achieve the specified base depth. The density shall be determined by the Engineer.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

SECTION 2.01

2.01.01 - Description: The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

Within the 100 feet where an embankment is to be made, the work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

The work of clearing and grubbing shall be performed at the point indicated on the plan view of the existing shoulder.

SECTION 3.08

3.08.01 - Description: The base shall consist of one or more courses, each 6 inches (150 millimeters) in thickness, and shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

3.08.02 - Material: ¾ inch Processed Aggregate shall be used for the base and shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.

3.08.03 - Construction Methods: The base shall be constructed in two courses of equal depth.

The base shall be constructed in two courses of equal depth.


The base shall be constructed in two courses of equal depth.

After the first course has been completed and bound as required, the second course shall be placed in order to achieve the specified base depth. The density shall be determined by the Engineer.

The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.


The work of reconstruction shall be performed at the point indicated on the plan view of the existing shoulder.

6 inches 1 1/4" Process Trap Rock Compacted Granular Base




INSTALLED AT A 60° ANGLE FROM CENTERLINE, DOWN SLOPE.



Access Drive Swale Detail




Access Drive & Parking Area Detail



Bituminous Concrete Access Drive Detail



Trench Drain




DOUBLE SILENCE W/ HAYBALE

1. All material shall be placed in the trench during construction and shall be compacted in place.
2. The trench shall be compacted in place during construction and shall be compacted in place during construction.
3. The trench shall be compacted in place during construction and shall be compacted in place during construction.
4. The trench shall be compacted in place during construction and shall be compacted in place during construction.
5. The trench shall be compacted in place during construction and shall be compacted in place during construction.
6. The trench shall be compacted in place during construction and shall be compacted in place during construction.
7. The trench shall be compacted in place during construction and shall be compacted in place during construction.
8. The trench shall be compacted in place during construction and shall be compacted in place during construction.
9. The trench shall be compacted in place during construction and shall be compacted in place during construction.
10. The trench shall be compacted in place during construction and shall be compacted in place during construction.
11. The trench shall be compacted in place during construction and shall be compacted in place during construction.
12. The trench shall be compacted in place during construction and shall be compacted in place during construction.
13. The trench shall be compacted in place during construction and shall be compacted in place during construction.
14. The trench shall be compacted in place during construction and shall be compacted in place during construction.
15. The trench shall be compacted in place during construction and shall be compacted in place during construction.
16. The trench shall be compacted in place during construction and shall be compacted in place during construction.
17. The trench shall be compacted in place during construction and shall be compacted in place during construction.
18. The trench shall be compacted in place during construction and shall be compacted in place during construction.
19. The trench shall be compacted in place during construction and shall be compacted in place during construction.
20. The trench shall be compacted in place during construction and shall be compacted in place during construction.

SITE LINE IMPROVEMENTS BEING COMPLETED
By
THE TOWN ENGINEER'S OFFICE

APPENDIX “B”


LOCATION MAP



Proposed Weston Dog Park
Entrance Driveway Off Davis Hill Road

APPENDIX "C"

TOPOGRAPHIC MAP



TOPOGRAPHIC MAP

APPENDIX “D”

TRAFFIC COUNTS


Graphical Plot of Automatic Traffic Recorder (ATR) Counts
Automatic Traffic Recorder (ATR) with 24 Hour Counts

DAVIS HILL ROAD
NORTH BOND LANE
6/1/17

TOTAL NUMBER OF VEHICLES 212

Weather
Sunny & Warm

NUMBER OF VEHICLES




TIME IN HOURS

DAVIS HILL ROAD
SOUTH BOUND LANE
6/1/17

TOTAL NUMBER OF VEHICLES 218

Weather
Sunny & Warm

NUMBER OF VEHICLES



North

ALL TRAFFIC
SOLUTIONS



A sign of the future.

Speed Summary Report

Generated by Rob Curcio from Town of Weston (CT)

on Jun 2, 2017 at 10:03:52 AM

Site: 117 Davis hill road, NB

Time of Day: 0:00 to 23:59

Dates: 5/26/2017 to 6/1/2017

Overall Summary

Total Days of Data: 2

Speed Limit: 25

Average Speed: 28.09

50th Percentile Speed: 27.00

85th Percentile Speed: 31.45

Pace Speed Range: 26 to 36

Minimum Speed: 5

Maximum Speed: 49

Display Status: Displayed Vehicle Speeds

Average Volume per Day: 218.5

Total Volume: 437



A sign of the future™

Volume By Time Report

Generated by Rob Curcio from Town of Weston (CT)

on Jun 2, 2017 at 10:04:38 AM

Speed Bins: Size 0, Range 1 to 100

Time View: By Day of Week (Avg Volumes)

Site: 117 Davis hill road, NB

Time of Day: 0:00 to 23:59

Dates: 5/26/2017 to 6/1/2017

Day of Week	0:00	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12:00	13:00	14:00	15:00	16:00	17:00	18:00	19:00	20:00	21:00	22:00	23:00	Total Num Vehicles
Wednesda	0	0	0	0	0	13	1	7	19	8	15	8	13	18	18	14	10	20	21	15	9	8	5	2	224
Thursday	0	0	0	1	1	0	5	9	14	10	10	15	8	18	16	13	16	17	14	11	14	8	6	6	212
Avg #	0	0	0	1	1	7	3	8	17	9	13	12	11	18	17	14	13	19	18	13	12	8	6	4	218

South

ALL TRAFFIC
SOLUTIONS



A sign of the future.

Speed Summary Report

Generated by Rob Curcio from Town of Weston (CT)

on Jun 2, 2017 at 10:07:00 AM

Site: 143 Davis Hill , SB

Time of Day: 0:00 to 23:59

Dates: 5/26/2017 to 6/1/2017

Overall Summary

Total Days of Data: 2

Speed Limit: 25

Average Speed: 23.53

50th Percentile Speed: 23.65

85th Percentile Speed: 27.03

Pace Speed Range: 22 to 32

Minimum Speed: 5

Maximum Speed: 45

Display Status: Did Not Display Vehicle Speeds

Average Volume per Day: 164.0

Total Volume: 328



Volume By Time Report

Generated by Rob Curcio from Town of Weston (CT)

on Jun 2, 2017 at 10:06:20 AM

Speed Bins: Size 0, Range 1 to 100

Time View: By Day of Week (Avg Volumes)

Site: 143 Davis Hill , SB

Time of Day: 0:00 to 23:59

Dates: 5/26/2017 to 6/1/2017

A sign of the future.

Day of Week	0:00	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12:00	13:00	14:00	15:00	16:00	17:00	18:00	19:00	20:00	21:00	22:00	23:00	Total Num Vehicles
Wednesda	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	37	15	9	6	8	11	3	0	21	110
Thursday	0	11	0	0	2	7	7	18	19	20	11	21	11	10	12	9	12	18	9	6	11	2	1	1	218
Avg #	0	6	0	0	1	4	4	9	10	10	6	11	6	5	6	23	14	14	8	7	11	3	1	11	164

APPENDIX “E”

TIME GAP STUDY

**TIME GAP STUDY
DAVIS HILL ROAD**

June 8, 2017

DAVIS HIL ROAD
June 8, 2017

Hours of Study 7:30 am to 9:30 pm

South Bound
Minutes & Seconds
Per Vehicle Gap

2:00 + (2 minutes Plus)

2:00+

2:00+ 0:23

2:00+ 1:35

1:17 0:42

0:48 2:00+

0:24 2:00+

2:00+ 1:11

0:36 2:00+

2:00+ 0:53

2:00+ 2:00+

0:46 0:25

1:18

2:00+

1:41

0:33

2:00+

2:00+

1:51

0:23

2:00+

2:00+

1:51

0:23

North bound
Minutes & Seconds
Per Vehicle Gap

0:41 1:24

0:49

1:27

2:00+

2:00+

1:37

2:00+

0:43

1:41

1:23

0:56

1:26

2:00+

1:50

0:32

2:00+

1:49

1:58

1:53

0:43

1:45

2:00+

2:00+

2:00+

DAVIS HIL ROAD
June 8, 2017

Hours of Study 12:00 pm to 1:30 pm

South Bound
Minutes & Seconds
Per Vehicle Gap

2:00 + (2 minutes Plus)
2:00+
1:26
2:00+
2:00+
2:00+
0:30
0:40
1:09
2:00+
2:00+

North bound
Minutes & Seconds
Per Vehicle Gap

2:00+
2:00+
1:38
0:59
2:00+
1:15
1:17
1:37
0:20

DAVIS HIL ROAD
June 8, 2017

Hours of Study 3:30 pm to 5:30 pm

South Bound
Minutes & Seconds
Per Vehicle Gap

1:30
2:00+ (2 minutes Plus)
2:00+
0:27
1:37
1:52
2:00+
1:10
2:00+
1:00
1:07
2:00+

North bound
Minutes & Seconds
Per Vehicle Gap

1:12
2:00+
2:00+
2:00+
2:00+
0:18
2:00+
2:00+
2:00+
1:01
2:00+
2:00+
0:15
0:15
2:00+
2:00+

APPENDIX “F”

ACCIDENT DATA



Weston Police Department Press Report

Incident Num	Date	Recv	Ofc I.D.	Officer	Nature	Act	Rpt	Location	House Number	Apr
12-419	2/1/2012	19:16	28	Miceli	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
12-1409	4/7/2012	22:36			Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 100	
13-609	2/8/2013	19:13			Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 103	
13-993	3/5/2013	14:25			Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
13-1198	3/17/2013	19:19	7	McInnis	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 54	
13-3968	8/4/2013	20:37	23	Forchione	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
13-4177	8/16/2013	20:14	28	Miceli	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 167	
13-5210	10/14/2013	14:10			Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
13-6109	12/16/2013	17:12	19	Brodacki	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
13-6117	12/17/2013	13:06	15	Ferullo	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 89	
14-2969	7/10/2014	12:06	24	Arnette	Motor Vehicle Accident	Cleared, No Action	No	Davis Hill Road	* 25	
14-3275	7/25/2014	23:06	31	McGraw	Motor Vehicle Accident	Department Info Only	No	10 Davis Hill Road	* 10	
14-4132	9/4/2014	3:22	21	Klein	Motor Vehicle Accident	MV Investigation	Yes	#47 Davis Hill Road		
14-5706	11/30/2014	19:06	24	Arnette	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
15-53	1/3/2015	15:44	25	Mogollon	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 81	
15-5426	10/10/2015	0:01			Motor Vehicle Accident	Motor Vehicle Arrest	Yes	Davis Hill Road	* 4	
16-2374	4/22/2016	12:04	33	Heibeck	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		
16-3967	7/12/2016	11:12	30	Greenfield	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road	* 103	
17-1412	2/21/2017	8:30	29	Cascone	Motor Vehicle Accident	MV Investigation	Yes	Davis Hill Road		

APPENDIX “G”

SAFE STOPPING SIGHT DISTANCE

CONNECTICUT DEPARTMENT OF TRANSPORTATION



HIGHWAY DESIGN MANUAL 2003 Edition

(U.S. Customary Units)

Design Speed (mph)	Downgrades			Level	Upgrades		
	-9%	-6%	-3%	0%	+3%	+6%	+9%
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)
20	130	120	120	115	110	110	105
25	175	165	160	155	150	145	140
30	230	215	205	200	200	185	180
35	290	275	260	250	240	230	225
40	355	335	315	305	290	280	270
45	430	400	380	360	345	335	320
50	510	475	450	425	405	390	375
55	595	555	520	495	470	450	435
60	690	640	600	570	540	515	495
65	790	730	685	645	615	585	565
70	895	825	775	730	690	660	635

Notes:

1. For grades intermediate between columns, use a straight-line interpolation to calculate SSD. For example:

V = 55 mph

G = -4.3%

$$\text{SSD} = 520 + \left(\frac{4.3 - 3}{6 - 3} \right) (555 - 520)$$

$$= 520 + 15.2$$

$$= 535.2 \text{ ft}$$

2. See Section 9-3.0 for application of SSD to crest and sag vertical curves.

STOPPING SIGHT DISTANCE**Figure 7-1A**

APPENDIX “H”

HIGHWAY CAPACITY MANUAL ROADWAY CLASSIFICATIONS

The three classes of two-lane highways are defined as follows:


- *Class I two-lane highways* are highways where motorists expect to travel at relatively high speeds. Two-lane highways that are major intercity routes, primary connectors of major traffic generators, daily commuter routes, or major links in state or national highway networks are generally assigned to Class I. These facilities serve mostly long-distance trips or provide the connections between facilities that serve long-distance trips.
- *Class II two-lane highways* are highways where motorists do not necessarily expect to travel at high speeds. Two-lane highways functioning as access routes to Class I facilities, serving as scenic or recreational routes (and not as primary arterials), or passing through rugged terrain (where high-speed operation would be impossible) are assigned to Class II. Class II facilities most often serve relatively short trips, the beginning or ending portions of longer trips, or trips for which sightseeing plays a significant role.
- *Class III two-lane highways* are highways serving moderately developed areas. They may be portions of a Class I or Class II highway that pass through small towns or developed recreational areas. On such segments, local traffic often mixes with through traffic, and the density of unsignalized roadside access points is noticeably higher than in a purely rural area. Class III highways may also be longer segments passing through more spread-out recreational areas, also with increased roadside densities. Such segments are often accompanied by reduced speed limits that reflect the higher activity level.

Exhibit 15-1 shows examples of the three classes of two-lane highway.

The definition of two-lane highway classes is based on their function. Most arterials or trunk roads are considered to be Class I highways, while most collectors and local roads are considered to be Class II or Class III highways. The primary determinant of a facility's classification is the motorist's expectation, which might not agree with the overall functional category of the route. For example, a major intercity route passing through a rugged mountainous area might be described as Class II if drivers recognize that high-speed operation is not feasible due to the terrain, but the route could still be considered to be in Class I.

Even Class III highways incorporate only uninterrupted-flow segments of two-lane highways. Occasional signalized or unsignalized intersections on any two-lane highway must be separately analyzed with the appropriate *Highway Capacity Manual* (HCM) methodologies in Chapter 18, Signalized Intersections, Chapter 20, All-Way STOP-Controlled Intersections, or Chapter 21, Roundabouts. The results must be carefully considered in conjunction with those of uninterrupted-flow portions of the facility to obtain a complete picture of probable operations.

Exhibit 15-1
Two-Lane Highway
Classification Illustrated



(a) Examples of Class I Two-Lane Highways



(b) Examples of Class II Two-Lane Highways



(c) Examples of Class III Two-Lane Highways


Base Conditions

The base conditions for two-lane highways are the absence of restrictive geometric, traffic, or environmental factors. Base conditions are not the same as typical or default conditions, both of which may reflect common restrictions. Base conditions are closer to what may be considered as ideal conditions (i.e., the best conditions that can be expected given normal design and operational practice). The methodology of this chapter accounts for the effects of geometric, traffic, and environmental factors that are more restrictive than the base conditions. The base conditions for two-lane highways are as follows:

- Lane widths greater than or equal to 12 ft,
- Clear shoulders wider than or equal to 6 ft,
- No no-passing zones,
- All passenger cars in the traffic stream,

APPENDIX “I”

FUTURE AREA GROWTH MAP



13.15 Acre Site No. 26
Possible Future Development

14.62 Acre Site No.'s 19, 23, 24
Possible Future Development

APPENDIX “J”

TWO LANE HIGHWAY USERS GUIDE

PERCENT TIME-SPENT-FOLLOWING

The Base Percent Time-Spent-Following (BPTSF_d) is estimated from HCM Equation 15-10, where a and b are constants drawn from HCM Exhibit 15-20. The Base Percent Time-Spent Following (BPTSF_d) is then adjusted using the No-Passing Zone Adjustment Factor ($f_{np,PTSF}$) from HCM Exhibit 15-21 to obtain the Percent Time-Spent-Following (PTSF_d) from HCM Equation 15-9.

PERCENT OF FREE-FLOW SPEED

The Percent of Free-Flow Speed (PFFS) is estimated from HCM Equation 15-11 and is included only in the analysis of Class III two-lane highways.

AUTOMOBILE LEVEL OF SERVICE AND PERFORMANCE MEASURES

In this section the calculated results of the Automobile analysis are displayed.

The Automobile Level of Service (LOS) is determined separately for Class I, Class II and Class III highways. Automobile Level of Service criteria for Two-Lane Highways from HCM Exhibit 15-3 for Class I, Class II and Class III highways respectively:

Class I:

	ATS (mi/h)	PTSF (%)
LOS A	>55	≤35
LOS B	>50-55	>35-50
LOS C	>45-50	>50-65
LOS D	>40-45	>65-80
LOS E	≤40	>80

LOS F exists whenever the demand flow in one or both directions exceeds the capacity of the segment.

Class II:

	PTSF (%)
LOS A	≤40
LOS B	>40-55
LOS C	>55-70
LOS D	>70-85
LOS E	>85

LOS F exists whenever the demand flow in one or both directions exceeds the capacity of the segment.

Class III:

	PFFS (%)
LOS A	>91.7
LOS B	>83.3-91.7
LOS C	>75.0-83.3
LOS D	>66.7-75.0
LOS E	≤66.7

LOS F exists whenever the demand flow in one or both directions exceeds the capacity of the segment.

Next, the capacity is determined under the prevailing conditions. HCM Equation 15-12 or HCM Equation 15-13 (or both) are applied and capacity is computed.

BICYCLE MODE

The user codes the Posted speed limit, Percent of segment with occupied on-highway parking, and Pavement rating for the highway being analyzed. The Flow rate in the outside lane is then calculated using HCM Equation 15-24. The Effective width of the outside lane is calculated using either HCM Equation 15-25, 15-26, or 15-27 depending on the paved shoulder width. Then the Effective speed factor is calculated using HCM Equation 15-30.

APPENDIX “K”

HIGHWAY CAPACITY SOFTWARE TRAFFIC VOLUMES YEAR 2017-2022

Phone:
E-Mail:

Fax:

Directional Two-Lane Highway Segment Analysis

Analyst
Agency/Co. WestCOG
Date Performed 7/24/2017
Analysis Time Period Peak PM Hour 5 - 6 pm
Highway Davis Hill Road
From/To Lords Highway East/South 1800'
Jurisdiction Weston
Analysis Year 2017
Description Existing LOS

Input Data

Highway class	Class 3	Peak hour factor, PHF	0.88
Shoulder width	0.0 ft	% Trucks and buses	2 %
Lane width	11.0 ft	% Trucks crawling	0.0 %
Segment length	0.3 mi	Truck crawl speed	0.0 mi/hr
Terrain type	Rolling	% Recreational vehicles	0 %
Grade: Length	- mi	% No-passing zones	100 %
Up/down	- %	Access point density	20 /mi

Analysis direction volume, Vd 19 veh/h
Opposing direction volume, Vo 18 veh/h

Average Travel Speed

Direction	Analysis (d)	Opposing (o)
PCE for trucks, ET	2.7	2.7
PCE for RVs, ER	1.1	1.1
Heavy-vehicle adj. factor, (note-5) fHV	0.967	0.967
Grade adj. factor, (note-1) fg	0.67	0.67
Directional flow rate, (note-2) vi	33 pc/h	32 pc/h

Free-Flow Speed from Field Measurement:

Field measured speed, (note-3) S FM	30	mi/h
Observed total demand, (note-3) V	37	veh/h
Estimated Free-Flow Speed:		
Base free-flow speed, (note-3) BFFS	-	mi/h
Adj. for lane and shoulder width, (note-3) fLS	-	mi/h
Adj. for access point density, (note-3) fA	-	mi/h

Free-flow speed, FFSd 30.3 mi/h

Adjustment for no-passing zones, fnp 2.4 mi/h

Average travel speed, ATSD 27.4 mi/h

Percent Free Flow Speed, PFFS 90.4 %

Percent Time-Spent-Following

Direction	Analysis (d)	Opposing (o)
PCE for trucks, ET	1.9	1.9
PCE for RVs, ER	1.0	1.0
Heavy-vehicle adjustment factor, fHV	0.982	0.982
Grade adjustment factor, (note-1) fg	0.73	0.73
Directional flow rate, (note-2) vi	30 pc/h	29 pc/h
Base percent time-spent-following, (note-4) BPTSFd	3.8 %	
Adjustment for no-passing zones, fnp	52.7	
Percent time-spent-following, PTSFd	30.6 %	

Level of Service and Other Performance Measures

Level of service, LOS	B	
Volume to capacity ratio, v/c	0.53	
Peak 15-min vehicle-miles of travel, VMT15	2	veh-mi
Peak-hour vehicle-miles of travel, VMT60	6	veh-mi
Peak 15-min total travel time, TT15	0.1	veh-h
Capacity from ATS, CdATS	1690	veh/h
Capacity from PTSE, CdPTSE	1700	veh/h
Directional Capacity	1690	veh/h

Passing Lane Analysis

Total length of analysis segment, Lt	0.3	mi
Length of two-lane highway upstream of the passing lane, Lu	-	mi
Length of passing lane including tapers, Lpl	-	mi
Average travel speed, ATSD (from above)	27.4	mi/h
Percent time-spent-following, PTSFd (from above)	30.6	
Level of service, LOSd (from above)	B	

Average Travel Speed with Passing Lane

Downstream length of two-lane highway within effective length of passing lane for average travel speed, Lde	-	mi
Length of two-lane highway downstream of effective length of the passing lane for average travel speed, Ld	-	mi
Adj. factor for the effect of passing lane on average speed, fpl	-	
Average travel speed including passing lane, ATSpl	-	
Percent free flow speed including passing lane, PFFSpl	0.0	%

Percent Time-Spent-Following with Passing Lane

Downstream length of two-lane highway within effective length of passing lane for percent time-spent-following, Lde	-	mi
Length of two-lane highway downstream of effective length of the passing lane for percent time-spent-following, Ld	-	mi
Adj. factor for the effect of passing lane on percent time-spent-following, fpl	-	
Percent time-spent-following including passing lane, PTSFpl	-	%

Level of Service and Other Performance Measures with Passing Lane

Level of service including passing lane, LOSpl	E	
Peak 15-min total travel time, TT15	-	veh-h

Bicycle Level of Service

Posted speed limit, Sp	55
Percent of segment with occupied on-highway parking	0
Pavement rating, P	3
Flow rate in outside lane, vOL	21.6
Effective width of outside lane, We	20.95
Effective speed factor, St	4.79
Bicycle LOS Score, BLOS	2.31
Bicycle LOS	B

Notes:

1. Note that the adjustment factor for level terrain is 1.00, as level terrain is one of the base conditions. For the purpose of grade adjustment, specific downgrade segments are treated as level terrain.
2. If v_i (v_d or v_o) $\geq 1,700$ pc/h, terminate analysis-the LOS is F.
3. For the analysis direction only and for $v > 200$ veh/h.
4. For the analysis direction only.
5. Use alternative Exhibit 15-14 if some trucks operate at crawl speeds on a specific downgrade.

HCS7: Two-Lane Highways Release 7.2

Phone:
E-Mail:

Fax:

 Directional Two-Lane Highway Segment Analysis

Analyst
Agency/Co. WestCOG
Date Performed 7/24/2017
Analysis Time Period Peak PM Hour 5 - 6 pm
Highway Davis Hill Road
From/To Lords Highway East/South 1800'
Jurisdiction Weston
Analysis Year 2022
Description 2022 LOS with Dog Park

 Input Data

Highway class	Class 3	Peak hour factor, PHF	0.88
Shoulder width	0.0 ft	% Trucks and buses	2 %
Lane width	11.0 ft	% Trucks crawling	0.0 %
Segment length	0.3 mi	Truck crawl speed	0.0 mi/hr
Terrain type	Rolling	% Recreational vehicles	0 %
Grade: Length	- mi	% No-passing zones	100 %
Up/down	- %	Access point density	20 /mi

Analysis direction volume, Vd 23 veh/h
Opposing direction volume, Vo 22 veh/h

 Average Travel Speed

Direction	Analysis (d)	Opposing (o)
PCE for trucks, ET	2.7	2.7
PCE for RVs, ER	1.1	1.1
Heavy-vehicle adj. factor, (note-5) fHV	0.967	0.967
Grade adj. factor, (note-1) fg	0.67	0.67
Directional flow rate, (note-2) vi	40 pc/h	39 pc/h

Free-Flow Speed from Field Measurement:

Field measured speed, (note-3) S FM	30	mi/h
Observed total demand, (note-3) V	45	veh/h

Estimated Free-Flow Speed:

Base free-flow speed, (note-3) BFFS	-	mi/h
Adj. for lane and shoulder width, (note-3) fLS	-	mi/h
Adj. for access point density, (note-3) fA	-	mi/h

Free-flow speed, FFSd	30.4	mi/h
-----------------------	------	------

Adjustment for no-passing zones, fnp	2.4	mi/h
Average travel speed, ATSD	27.3	mi/h
Percent Free Flow Speed, PFFS	90.1	%

Percent Time-Spent-Following

Direction	Analysis(d)	Opposing (o)
PCE for trucks, ET	1.9	1.9
PCE for RVs, ER	1.0	1.0
Heavy-vehicle adjustment factor, fHV	0.982	0.982
Grade adjustment factor, (note-1) fg	0.73	0.73
Directional flow rate, (note-2) vi	36 pc/h	35 pc/h
Base percent time-spent-following, (note-4) BPTSFD	4.5 %	
Adjustment for no-passing zones, fnp	52.7	
Percent time-spent-following, PTSFD	31.2 %	

Level of Service and Other Performance Measures

Level of service, LOS	B	
Volume to capacity ratio, v/c	0.53	
Peak 15-min vehicle-miles of travel, VMT15	2	veh-mi
Peak-hour vehicle-miles of travel, VMT60	7	veh-mi
Peak 15-min total travel time, TT15	0.1	veh-h
Capacity from ATS, CdATS	1690	veh/h
Capacity from PTSF, CdPTSF	1700	veh/h
Directional Capacity	1690	veh/h

Passing Lane Analysis

Total length of analysis segment, Lt	0.3	mi
Length of two-lane highway upstream of the passing lane, Lu	-	mi
Length of passing lane including tapers, Lpl	-	mi
Average travel speed, ATSD (from above)	27.3	mi/h
Percent time-spent-following, PTSFD (from above)	31.2	
Level of service, LOSd (from above)	B	

Average Travel Speed with Passing Lane

Downstream length of two-lane highway within effective length of passing lane for average travel speed, Lde	-	mi
Length of two-lane highway downstream of effective length of the passing lane for average travel speed, Ld	-	mi
Adj. factor for the effect of passing lane on average speed, fpl	-	
Average travel speed including passing lane, ATSpl	-	
Percent free flow speed including passing lane, PFFSpl	0.0	%

Percent Time-Spent-Following with Passing Lane

Downstream length of two-lane highway within effective length of passing lane for percent time-spent-following, Lde	-	mi
Length of two-lane highway downstream of effective length of the passing lane for percent time-spent-following, Ld	-	mi
Adj. factor for the effect of passing lane on percent time-spent-following, fpl	-	
Percent time-spent-following including passing lane, PTSFpl	-	%

Level of Service and Other Performance Measures with Passing Lane

Level of service including passing lane, LOSpl	E	
Peak 15-min total travel time, TT15	-	veh-h

Bicycle Level of Service

Posted speed limit, Sp	55
Percent of segment with occupied on-highway parking	0
Pavement rating, P	3
Flow rate in outside lane, vOL	26.1
Effective width of outside lane, We	20.74
Effective speed factor, St	4.79
Bicycle LOS Score, BLOS	2.44
Bicycle LOS	B

Notes:

1. Note that the adjustment factor for level terrain is 1.00, as level terrain is one of the base conditions. For the purpose of grade adjustment, specific downgrade segments are treated as level terrain.
2. If v_i (v_d or v_o) $\geq 1,700$ pc/h, terminate analysis-the LOS is F.
3. For the analysis direction only and for $v > 200$ veh/h.
4. For the analysis direction only.
5. Use alternative Exhibit 15-14 if some trucks operate at crawl speeds on a specific downgrade.

APPENDIX “I”

INTERSECTION ANALYSIS

HCS7 Two-Way Stop-Control Report


General Information

Analyst	
Agency/Co.	WestCOG
Date Performed	7/24/2017
Analysis Year	2022
Time Analyzed	PM Peak Hour 5 - 6 pm
Intersection Orientation	North-South
Project Description	Proposed Dog Park

Site Information

Intersection	Dog Park Driveway
Jurisdiction	Weston
East/West Street	Dog Park Driveway
North/South Street	Davis Hill Road
Peak Hour Factor	0.92
Analysis Time Period (hrs)	1.00

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	1	0		0	0	0	0	0	1	0	0	0	1	0
Configuration			LR							LT						TR
Volume, V (veh/h)		3		3						3	20				19	3
Percent Heavy Vehicles (%)		0		0						2						
Proportion Time Blocked																
Percent Grade (%)	-10															
Right Turn Channelized	No				No				No				No			
Median Type/Storage	Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		4.40		5.20						4.12						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.50		3.30						2.22						

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			6							3						
Capacity, c (veh/h)			1027							1590						
v/c Ratio			0.01							0.00						
95% Queue Length, Q ₉₅ (veh)			0.0							0.0						
Control Delay (s/veh)			8.5							7.3						
Level of Service, LOS			A							A						
Approach Delay (s/veh)	8.5								0.9							
Approach LOS	A															

REFERENCES

1. Weston Police Department
2. Connecticut Department of Transportation
3. Western Connecticut Council of Governments
4. Highway Capacity manual